

Automated Machine Guidance (AMG) 3D Pilot Projects

Steven Buck and Jason Christopher

AMG


CONSTRUCTION



Photo Courtesy of FHWA

DESIGN

VS.





CHANGING THE MINDSET


PLANS PRODUCTION


=
DATA PRODUCTION




D5 Pilot Project

New construction of a 3.5 mile long trail





FDOT SYMPOSIUM




FDOT SYMPOSIUM

Goal #1

SIGNED & SEALED 3D MODEL FOR AMG CONSTRUCTION




No. 00000










Contractor Input



Contractor Input

- Gaps in the model = problems
- Need enough detail to construct




Goal #1

HOW IS THIS DIFFERENT?


- More detail modeling
- Additional QC of model
- Locking the model file
 - 3D sign and seal



How much detail?



OR





Goal #2

NexGen PLANS DATA PRODUCTION



INDEX OF ROADWAY PLANS

SHEET NO.	SHEET DESCRIPTION						
1	KEY SHEET						
2	SIGNATURE SHEET						
3	SUMMARY OF PAY ITEMS						
4-7	TYPICAL SECTIONS						
8	OPTIONAL MATERIALS TABULATION						
9	SUMMARY OF DRAINAGE STRUCTURES						
10	PROJECT LAYOUT						
11	CURVE AND COORDINATE DATA SHEET						
12	GENERAL NOTES						
13-24	TRAIL PLAN PROFILE SHEETS						
-25-30	DETAIL SHEETS						
-31-36	GRADING SHEETS						
37-38	DRAINAGE STRUCTURES						
-39	SOUTH TRAILHEAD CROSS SECTION PATTERN SHEET						
40-46	SOUTH TRAILHEAD CROSS SECTIONS						
47	NORTH TRAILHEAD CROSS SECTION PATTERN SHEET						
48 66	NORTH TRAILHEAD CROSS SECTIONS						
-67	TRAIL CROSS SECTION PATTERN SHEET						
68-89	TRAIL CROSS SECTIONS						
90-92	STORMWATER POLLUTION PREVENTION PLAN						
93	TRAFFIC CONTROL PLAN GENERAL NOTES						
CTL-1	PROJECT NETWORK CONTROL SHEET						
GR-1	AUGER BORING RESULTS						
GR-2	TRAIL SOIL SURVEY						
SQ-1 - SQ-8	SUMMARY OF QUANTITIES						



NexGen Plans

104 PLAN SHEETS
VS.
31 PLAN SHEETS




NexGen Plans


HOW DO YOU REVIEW???

- Internal Stakeholders
- External Stakeholders














Internal Stakeholders

One on One Interviews Interactive Review Meetings



External Stakeholders

FDEP





Orange County GOVERN



Lake County



Utilities



Permit Review

Drainage Report NexGen Plans 2D KMZ with Contours





Utility Review

Provided 2D CADD Files Received CADD/Shape Files



Major Challenges

Changing the Mindset
Reviews
CEI
Bidding



Next Steps

DECEMBER 4TH LETTING CEI SOP



Polk Parkway Resurfacing MP 0-8 (3D/AMG)

Project Overview & Objectives



General

- 8 Miles of 4-lane divided urban limited access toll facility
- Multiple Interchanges
- Moderately complex geometry

Milling & Resurfacing

- Full Depth Crack Repairs
- Cross Slope Correction

Roadside & Safety Improvements

- Misc. Barrier
- Minor Drainage
- Traffic (S&PM, Lighting, Signals)

Require Automated Machine Guidance (AMG) for milling & resurfacing Deliver Roadway &
Drainage
components in 3D –
Signed & Sealed
Contract Document

Ensure constructible and biddable contract documents

NexGen Plans –
Use large format
plans in conjunction
with the 3D model
to reduce the 2D
plans



Polk Parkway Resurfacing MP 0-8 (3D/AMG) Contract & Information Only Documents





Sign & Seal 3D Model

- Roadway & Drainage only
- CADD/Model Files (*.DGN)
- LandXML files (AMG Paving)

Modified Special Provisions

- MSP 001 Definition of "Plans"
- MSP 327 Milling
- MSP 330 Superpave (Resurfacing)

Sign & Seal 2D Plans

- Temporary Traffic Control
- Structures
- Signalization
- S&PM/Lighting (Large Format)

2D "For Information Only" Plans

- Roadway Large Format
 - Project Layout
 - Roadway/Drainage
 - Cross Sections (Review Only)
- S&PM/Lighting Large Format
 - Combined S&PM & Lighting

Removed from 2D Plans

- Summary of Pay Items
- Curve & Coordinate Data Sheets
- Roadway/Drainage Plan Sheets
- Roadway Cross Sections
- Drainage Structures Sheets



Polk Parkway Resurfacing MP 0-8 (3D/AMG)







Obtained approval for objectives from Central Office and Turnpike Leadership

Held multiple Construction and CEI Industry Forums Created a
"Plans-Data
Production
Cross-Walk"
to track
changes

Created
traditional
drainage
structure sheets
for UAO
coordination
only

















Project
Delivery
Workshops
with
Department &
Consultant
Stakeholders

Held multiple
3D Model
Review
Workshops
for Phase
Submittal ERC
Reviews

Created NexGen Plans – Large Format Plans where practical Coordinated with Central Office for Modified Special Provisions, NexGen Plans, 3D model technical support and state of the practice inquiries



Polk Parkway Resurfacing MP 0-8 (3D/AMG) Plan-Data Cross Walk

	Traditional		Proposed		
Item Description	Format	S&S?	Format	S&S?	Comments
Roadway Plans					
Key Sheet	11x17	Y	11x17	Y	Follows FDM and TDH
Signature Sheet	11X17	Υ	11x17	Υ	Follows FDM and TDH, with "FIO" sheets noted
Summary of Pay Items	11X17	Y	Letter	N	Include in bid package separate from plans
Ti. a.l. Cardinar	11X17	Υ	11x17	Υ	These will be S&S since no useful solution could be
Typical Sections					found to include the information in the 3D model.
Typical Section Details	11X17	Υ	11x17	Υ	These will be S&S since no useful solution could be
Typical Section Details					found to include the information in the 3D model.
Summany of Drainago Structuros	11X17	Y	11x17	Y	Follows FDM and TDH, with the addition of invert and
Summary of Drainage Structures	TIAIT				top elevations in the table.
Optional Materials Tabulation	11X17	Υ	11x17	Υ	Follows FDM and TDH
General Notes	11X17	Υ	11x17	Υ	Follows FDM and TDH
			Roll plot		Only information provided is stationing, PC/PT/PI
		Y			locations, bearings, begin/end project, and
Project Layout	11X17			N	identification of roadway roll plot limits; station
					equations and curve data will not be provided since
					this information can be pulled from the S&S 3D model.
Coordinate & Curve Data	11X17	Y	None	N/A	Information traditionally provided on these sheets can
Coordinate & Curve Data	HAIT		None	IWA	be pulled directly from S&S 3D model
					All proposed design elements are shown and labeled.
	11X17	Y	Roll plots	N	For bidding assistance, begin/end station labels and
Roadway Plan					other proposed geometry will be included on the roll
					plot.
	On the sheet	Y	Model metadata		Information traditionally provided in plan labels will be
					provided within the intelligence of the 3D design
Plan Labels				Y	elements, in the form of metadata that can be read
					from the 3D model
Drainage Structures	(11X17	Y	In 3D model	Y	All information needed for construction (grate/top/inlet
					elevations, invert elevations, pipe size, etc.) provided
					as metadata in the 3D model. The same information is
					also provided in the Summary of Drainage Structures.
Cross Section Pattern	11X17	Y	None	N/A	Not needed
					Include in reviews through design, remove from
Cross Sections	11X17	Y	Roll plots	N	contract set
SWPPP	11X17	Υ	11x17	Υ	Follows FDM and TDH
Erosion Control Details	11X17	Y	11x17	Y	Follows FDM and TDH
TTC General Notes	11X17	Y	11x17	Y	Follows FDM and TDH
TTC Phase Typicals	11X17	Y	11x17	Y	Follows FDM and TDH
TTC Details	11X17	Y	11x17	Y	Follows FDM and TDH
TTC Detours	11X17	Y	11x17	Y	Follows FDM and TDH
Utility Adjustments	(11X17)	Y	Roll plots	N	Follows FDM and TDH, provided on roadway roll plots
Structures Details	11X17	Y	11x17	Y	Follows FDM and TDH
Summary of Quantities	11X17	Y	11x17	Y	Follows FDM and TDH
3D Model	DGN/XML	N	DGN/XML	Y	





	Traditional		Proposed		
Item Description	Format	S&S?	Format	S&S?	Comments
SAPM Plans					
Key Sheet	11x17	Υ	11x17	Y	Follows FDM and TDH
Signature Sheet	11X17	Υ	11x17	Υ	Follows FDM and TDH
Tabulation of Quantities	11X17	Υ	11x17	Y	Follows FDM and TDH
General Notes	11X17	Υ	11x17	Υ	Follows FDM and TDH
Plan Sheets	11X17	Y	Roll plots	Y	Other than being laid out on roll plots, the information provided will follow FDM and TDH requirements
Guide Sign Worksheets	11X17	Υ	11x17	Υ	Follows FDM and TDH
Cross Sections	11X17	Υ	11x17	Υ	Follows FDM and TDH
Special Details	11X17	Υ	11x17	Υ	Follows FDM and TDH
Signalization Plans					
Key Sheet	11x17	Υ	11x17	Υ	Follows FDM and TDH
Signature Sheet	11X17	Υ	11x17	Υ	Follows FDM and TDH
Tabulation of Quantities	11X17	Υ	11x17	Υ	Follows FDM and TDH
General Notes	11X17	Υ	11x17	Υ	Follows FDM and TDH
Plan Sheets	11X17	Υ	11x17	Υ	Follows FDM and TDH
Guide Sign Worksheets	11X17	Υ	11x17	Υ	Follows FDM and TDH
Cross Sections	11X17	Υ	11x17	Y	Follows FDM and TDH
Special Details	11X17	Υ	11x17	Υ	Follows FDM and TDH
Mast Arm Tabulation Sheet	11X17	Υ	11x17	Y	Follows FDM and TDH
Lighting Plans (included in SAPM s	et)				
Tabulation of Quantities	11X17	Υ	11x17	Υ	Follows FDM and TDH
General Notes	11X17	Υ	11x17	Υ	Follows FDM and TDH
Pole Data	11X17	Υ	11x17	Y	Follows FDM and TDH
Service Point Details	11X17	Υ	11x17	Υ	Follows FDM and TDH
Plan Sheets	11X17	Y	Roll plots	Y	Other than being laid out on roll plots, the information provided will follow FDM and TDH requirements
Special Details	11X17	Υ	11x17	Υ	Follows FDM and TDH



Polk Parkway Resurfacing MP 0-8 (3D/AMG) Project Management Considerations



Identify & define pilot project objectives and stake holders prior to selecting a candidate project. Ensure stakeholders are on board or that their issues/concerns can be mitigated.

Engage team members that are curious, interested, and passionate about 3D design delivery. Select trusted partners to come along for the ride.

Broadly scope & negotiate the staff hours – anticipate and account for unknowns and stakeholder needs to avoid adverse impacts to your Production & Letting commitments.

Schedule accordingly and anticipate additional time needed to resolve pilot project's technical issues and stake holder coordination.

3D delivery requires a significant change in work flow for Department ERC reviews and WMD/Utility coordination & reviews.

3D delivery is new and challenging. It is also exciting and manageable – Try it!



3D Model, AMG, and NexGen Plans

- 3D Model Signed & Sealed Contract Document
- NexGen Plans Large format plans with the 3D model
- Plans Data Production Cross Walk
- Phase Submittal Reviews (different approaches)
- 3D Model Level of Detail
- CEI Scope Development (different approaches)
- Modified Special Provisions



Challenges for Further Exploration

- 3D Model Revisions
- 3D Model As-Builts
- Data Storage and Archiving of Files
- Florida Board of Professional Engineers Rules Changes
- External Stake Holder Coordination & Acceptance
- Evolution of design and CEI scopes
- Department Phases Reviews and Reviewer Training
- Updates to Standard Specifications and Basis Estimates





THANK YOU

STEVEN.BUCK@DOT.STATE.FL.US

JASON.CHRISTOPHER@DOT.STATE.FL.US

