


Halls River Bridge Lessons Learned

Bren George-Nwabugwu Sr. (FHWA), Zach Stringer (FDOT), & Michael Ojo (FDOT)

MICHAEL O. OJO, P.E. (FDOT D-7 Design)

PROJECT OVERVIEW

- **☐** Type of Project
- ☐ Length of Project:
 - 185 FT bridge
 - 1600 FT approaches
- □ Construction Cost = \$6.1M
- ☐ Original Contract Time = 310 days



OUTLINE


□ Proprietary Materials ☐ Site Conditions ☐ Variability in Riverbed Strata **☐** Location Challenges ■ Maintenance Agreement ☐ Excavation for Sheet Piles **Innovative Materials Changes between Design phase** and Construction

BRIDGE COMPOSITION (BEFORE)






BRIDGE COMPOSITION (AFTER)



USE OF PROPRIETARY MATERIALS

Two Sole Source Items

- ☐ Hybrid Composite Beam (HCB) with HC Bridge Company
- □ Carbon Fiber Composite Cable (CFCC)with Tokyo Rope, Japan



ISSUES

- ☐ Material (CFCC) from Japan
- ☐ Long lead time after purchase order
- □ Need for additional pile length




SUGGESTIONS

- ☐ Official commitment from the producer or supplier
- More geotechnical information additional soil boring
- Possibility of separate contract for the materials
- ☐ If possible, avoid proprietary materials

PROJECT LOCATION

- ☐ Moderate daily traffic
- ☐ Limited right of way
- **□** Off-system roadway
- □ No alternate route



ISSUES

- □ Traffic Control Approach
- Emergency vehicles
- Coordination with law enforcement and schools
- Limited right of way
- □ ACROW bridge vs phased const.
 - ROW purchase/ TCE
 - Wetland
 - Permit requirements



SUGGESTIONS

☐ Consider the unforeseen in the equation





Osprey on top of the crane

Osprey relocation

Crash

SUGGESTIONS

- ☐ Use of ACROW bridge
- □ Location consideration
- ☐ Law enforcement and emergency personnel



MAINTENANCE AGREEMENT

- ☐ Two parts of Maintenance Agreement
 - Maintenance after construction
 - Off system Construction agreement
- □ Project funding
 - No State money
 - FHWA pays 100% of participating items
 - FHWA pays 0% of non participating items/work

OFF SYSTEM CONSTRUCTION AND MAINTENANCE AGREEMENT

("Agreement")

Between

STATE OF FLORIDA, DEPARTMENT OF TRANSPORTATION ("FDOT")

and

CITRUS COUNTY, FLORIDA a political subdivision of the State of Florida ("LOCAL GOVERNMENT")

WHEREAS, the State of Florida Legislature has approved and mandated the FDOT to complete the various projects included in the FDOT's Work Program; and

WHEREAS, included in the FDOT Work Program is Project Number FM 430021-1-52-01 (County Road 490A (Halls River) from west of Halls River to east of Halls River) located in Citrus County, Florida, ("Project"), which is not located on the State Highway System; and

WHEREAS, the parties agree that it is in the best interest of each party for the FDOT to undertake and to complete all aspects of the Project, including but not limited to the design, construction, construction inspection, utilities, permits, and other associated tasks; and

WHEREAS, the LOCAL GOVERNMENT shall maintain the Project upon notice from the FDOT as set forth in this Agreement; and

WHEREAS, the FDOT will, upon approval of federal participation by the Federal Highway Administration ("FHWA"), undertake the Project.

MAINTENANCE AGREEMENT

- ☐ FHWA requirement☐
 ☐ To be executed before letting
- ☐ Coordination with the county ☐ Begin as early as possible

CONTRACT FILE INDEX


Financi	al Project IDProposal/Contract ID
ATTAC	HMENTS (check if included or list expected date of transmittal to Central Office)
	Calendar Days Recommendation
	Preliminary Engineering Certification*
	Utility Certification
	Status of Environmental Certification (Form 650-050-13 (Federally-Funded Project) or 650-050-14 (State-Funded Project))
	Permit Transmittal Memo**
	Railroad Clear Letter
	FDOT/FGT Encroachment Agreement
	Certificate for Construction (Form 575-095-05)
	Executed copy of MMOA for Projects with Patterned Pavement
	Approval if SP0080701B Computation of Contract Time is used.
	Landscape Exception Approval per Engineering and Operations Bulletin 13-1
ONo (Yes Project exempt from FHWA oversight under agreement dated November 15, 2012
ONo (Yes Right of Way Certification was mailed to State R/W Administrator
ONo (Yes N/A Local Funds Agreement sent to Office of Comptroller
ONo €	Yes ONA Local Funds Sent to Office of Comptroller
	Yes N/A Project is Federally Funded off the State Highway System, requiring a Maintenance Agreement.
	If yes, a Maintenance Agreement (Number) was executed or . A copy is available upon request.
* Inclu	ude if federally funded.
	t have District Secretary Approval if Permits are not received by Authorization (Federally
	Projects Only).
Note:	If project is federally funded and has a state funded "Goes With", please provide the same documentation as required for a federally funded project.
Name:	Date:
_	Print Name of Project Manager/Other Title

Zachary W. Stringer, FDOT D-7 Construction PM

CONSTRUCTION – INNOVATIVE MATERIALS

- Consider a Mandatory Pre-bid to discuss
 - Cost and time frames for additional testing GFRP
 - Long lead items Tokyo Rope CFRP Implications on pile casting
 - Unforeseen potential costs to producers Rental for tensioning device - CFRP

CONSTRUCTION – INNOVATIVE MATERIALS









Construction - Innovative Materials





Construction – Innovative Materials

SITE CONDITIONS







Site Conditions

Outstanding Florida Waterway

OUTSTANDING FLORIDA WATERWAY

- Strict Permit Conditions
 - Mixing Zone of 41 NTUs beyond background readings and 1 NTU outside of that
 - Plans only allowed for floating turbidity curtain
 - Preformed holes for piles and excavation for sheet wall required additional measures

OUTSTANDING FLORIDA WATERWAYS







Outstanding Florida Waterway

VARIABILITY IN RIVERBED STRATA

- Pile depths
 - Plans and two additional sets of SPTs all indicated that we shouldn't need any pile longer than 85' however we had four adjacent piles with the following driven lengths (141 LF, 37 LF, 127 LF, and 67 LF) each spaced 10' 4.5" apart.





Pile Depths

PILE DEPTHS

- Innovative Materials
 - Splice materials
 - Index called for CFRP Dowels but no approved producers
 - No mechanical splice approved for CFRP Piles

PILE SPLICES





PILE SPLICES







Pile Splices

EXCAVATION FOR SHEET PILE

- Limited Right of Way prevented large equipment
- Innovative materials influenced design decisions
 - No tie-back system without carbon steel
- •\$650K Change Order for redesign

EXCAVATION FOR SHEET PILE








Deadman and Anchor Seawall



Changes Between Design and Construction

CHANGES BETWEEN DESIGN AND CONSTRUCTION

- Margarita Grill resumed construction and opened in September of 2017
 - Additional drainage installed prior to construction needed incorporated into the proposed system in the area
 - Access needed to be maintained for increased traffic which was not anticipated during design



Changes Between Design and Construction

Questions???